RG104 E-1 Box 146

William Sellers, President.
John Sellers, Jr., Vice-President.
George H. Sellers, Gen'l Sup't.
William P. Sellers, Secretary.
William H. Connell, Treas.

Edge Moor Iron Company,

P.O. Wilmington, Del.

Edge Moor, July 16, 1887. 18

Hon. Daniel M. Fox,

Supt. U. S. Mint,

Philada, Pa.

Dear Sir;

This will advise you that we have our work on your Boiler Improvement at the U. S. Mint completed as far as is possible under existing hindrances beyond our control.

We have yet to run the drip pipe from heater to blow-off well, this cannot be put in until you have the duct completed to lay it in; we have also the attachment from heater to the water pipe connecting to street main to run, we are advised that you have to lay a new pipe out to the street main as the old one is deficient and stopped up. We have yet to put on the covering on steam and water pipe, and put on the finishing coat of cement over top of boiler arches, both of which we prefer to leave until working pressure of steam has been raised on the boilers, provided it has your approbation and we are exonerated from any penalty as is specified for in contract for non completion of the work. We, of course, hold ourselves in readiness, at short notice, to make the attachments and complete the covering of pipes

RG104 E-1 Box 146

and cementing boiler covering.

You will kindly provide the necessary best Lehigh anthracite pea coal for starting and testing the boilers, and oblige,

Yours truly,

EDGE MOOR IRON COMPANY,

Geo H Sellers

GEN'L SUPT.

RG104 E-1 Box 146

Ed.

Edgmur Iron Co.
July 16/87

Work on Boiler improvement at Mine is completed, as far as possible. Cannot run the drip pipe from heater to blow off until duct is completed &c. Request that the best Lehigh Anthracite pea coal be provided for starting & testing the boilers.

Recd
July 17/87

NARA RG104, Entry 1, Box 146

[Abstract:] Work on Boiler improvement at Mint is completed as far as possible…

Edge Moor Iron Company,
Edge Moor,
July 16, 1887

Hon. Daniel M. Fox,
Supt. U.S. Mint,
Philada, Pa.

Dear Sir;

This will advise you that we have our work on your Boiler Improvement at the U.S. Mint completed as far as is possible under existing hindrances beyond our control.

We have yet to run the drip pipe from heater to blow-off well, this cannot be put in until you have the duct completed to lay it in; we have also the attachment from heater to the water pipe connecting to street main to run, we are advised that you have to lay a new pipe out to the street main as the old one is deficient and stopped up. We have yet to put on the covering on steam and water pipe, and put on the finishing coat of cement over top of boiler arches, both of which we prefer to leave until working pressure of steam has been raised on the boilers, provided it has your approbation and we are exonerated from any penalty as is specified for in contract for non completion of the work. We, of course, hold ourselves in readiness, at short notice, to make the attachments and complete the covering of pipes and cementing boiler covering.

You will kindly provide the necessary best Lehigh anthracite pea coal for starting and testing the boilers, and oblige.

Yours truly,
Edge Moor Iron Company,
Geo. H. Sellers
Gen'l Supt.